



Asansol Girls' College

(NAAC Accredited with 'A' Grade)

(GOVT. SPONSORED)

Affiliated with The Kazi Nazrul University

Dr. Anjali Roy Sarani, Asansol - 713304

Ph. 0341-2257107 (Day), 2254098 (Morn.), 2257600 (Principal), Fax : 0341-2257107

Website : www.agc.ac.in • E-mail :

mail.agcorgin@gmail.com

Ref. No. 020/19

Date 13.02.2019

Re: Asansol Girls' College, Asansol-4

Ref:.....

Underground reinforced cement concrete reservoir for storage of filtered water in common place of Girls' Hostel Old & new.

Estimated Amt: Rs.231706.00

Sealed quotation is invited from experienced contractor with the proper documents to do the above job with following details.

Reservoir will be suitably located and constructed as per advice of the college authority.

Size of Reservoir will be 6550lg x 2900wide x 2100 High. With apx. Capacity of 27 CU.M. and of r.c.c. construction with M20 grade cement concrete mixed with 0.2% hydroinsalution compound (VIZ- SIKA). All side and botton wall will be 200th. Top slab will be 150th with necessary holes left for inlet and outlet lines and 550 I/D Manhole in each chamber. Reservoir will have two chambers with a cross r.c.c partition wall of 150th. Top of the tank will be 300 above G.L. At U/S of Tank P.C.C. Mud mat (1:3:6) of 150th will be provided. High quality PVC specials for inlet / outlet/overflow etc. will be fixed in concrete, Manhole C.I. cover and Ring, all PVC spirals are within the scope of this quotation. All inlet/outlet/overflow will be temporarily plugged with suitable PVC Plugs.

Good quality material for shuttering, I.S.I grade cement (A.C.C, Ambuja, Konark Laferge etc.) SAIL/TATA make reinforcement to be used. On side wall of each chamber, one 150 dia hole is to be left for fixing overflow line at U/S of top slab.

During quoting of rate in attached format the contractor should take the guide lines of P.W.D's schedule effective 01.11.2017 All rates should include 12% G.S.T., 3% contingency, 1% labour welfare cess etc. 12% GST will be deducted from the bill.

All building materials, staging , tools, tackles , labour cost , labour insurance/ Provident Fund/ Medical, water/ electricity accident benefit will be under the scope of the contractor U.O.S.

Estimated Amount: Rs. 231706.00 (Rupes Two lakh Thirty One thousand Seven hundred Six Only).

Time of completion to be three months, From the date of acceptance of work order.

Defect liability period will be 6 (Six) month. During this period any defect will have to be repaired /rectified by the contractor with his own cost.

S.D. Money will be deducted 10% of the bill amount and will be returned to the contractor after expiry of D.L.P. to the satisfaction of the client.

The contractor is advised to fill up the format and to quote the total amount for construction of reservoir in complete. The contractor must have Trade License I.T, P.T, and GST, E.S.I, E.P.F. registration with upto-date validity and with adequate experience to do the above job and he must attach documentary proof for these. All these document must be submitted in envelope marked-I

The contractor can purchase the quotation papers (duly stamped and signed by college Authority) from the college office from 13.02.2019 to 23.02.2019 against cash price of Rs. 200.00(Rupees two hundred only) and will submit in sealed cover latest by 26.02.2019. In the same envelop, price bid will be submitted in separate envelop Mark Part-II. Other details and document will be submitted in another envelop Part-I.

College Authority has got every right to change the specified dates of the quotation or to cancel the quotation without assigning any reason.

The terms & Condition of college Tender will be applicable. Copy of this Quotation duly signed by Contractor is to be submitted in Part-I- envelop.

Date: 012.02.2019


Signature of Vice Principal

Asansol Girls' College
Vice Principal
Asansol Girls' College