



Asansol Girls' College

(NAAC Accredited with 'A' Grade)
(GOVT. SPONSORED)

Affiliated with The Kazi Nazrul University
Dr. Anjali Roy Sarani, Asansol - 713304

Ph. 0341-2257107 (Day), 2254098 (Morn.), 2257600 (Principal)

Website : www.agc.ac.in • E-mail : mail@agc.ac.in

Ref. No. 32/23.....

Date 28.03.2023

N.I.T. No. 32/23 dt. 28/03.2023

Asansol Girls' College, Asansol-4

Subject: Rebuild of Broken existing brick (C.B.W.) Boundary wall on east side (i.e. Rail line side) of college building with structural concrete (M20) frame work and cement brick work (1:6) with cement plaster (1:6) and cement wash.

TENDER NOTICE

About 16 M length of existing brick boundary wall on railway side of abt 2.5 M high from ground level has collapsed due to ageing and continual vibration from Main Rly track (Live). It is proposed to rebuild the collapsed portion with necessary r.c.c. frame work embracing 125m/m thick c.b.w to absorb the track vibration and its shock.

5nos r.c.c. pillar in 4nos span of 4 M each will be provided with nominal R.C.C. foundations at U/S of pillars. Each columns will be 200 M/M wide X 250 M/M deep with 4 nos 12 Dia bar and 8 Dia stirrup @ 200 C/C. In between column in each span 3 nos r.c.c. beams (one at top level, one at Grd level and third one at Middle level) to be provided. Beam size to be 125 wide X 200 M/M deep with 4 nos 10 Dia straight bars and 8 Dia stirrup @ 250 C/C. Grade of concrete in beams and columns will be M20. U/S of col-faln will be 600 M/M below grd level . In between beams 125th C.B.W.(1:4) will be provided. Inter face of r.c.c frame and brick wall will have rough finish to have proper bondage. 20 M/M cement plaster (1:6) will be provided on either side of new construction proposed wall will have 2 coat of cement wash. All other instruction as required will be provided by E.I.C. of college. All construction will follow specified terms and condition of college tender as stipulated in college website U.O.S.

Estimated amount including with 12% . G.S.T. (6% for State and 6% G.S.T. for Central) 1% Labour welfare cess and 3% contingency = Rs. 93703.00 (Rupees Ninety three thousand Seven hundred and three only)


Vice-Principal
Asansol Girls' College




Sealed Tender is invited from **03.04.2023 to 24.04.2023** in two part system in standard format from experienced contractors having I.T., P.T., Trade License certificate, with G.S.T, P.F, registration.

Standard format will be available from the college office against payment of Rs. 200.00 in cash on **31.03..2023 to 22.04.2023** in office hours. Earnest money of Rs. 2000/- is to be paid during submission of tender papers in sealed envelope Marked (1) in form of Bank draft in favour of Vice Principal, Asansol Girls' College.

All documents of credential, E.M. etc. are to be put in an envelope mkd (1) and Price bid in **standard format received from college office** with signature along with tender papers is to be put in another sealed envelope mkd(2) this two sealed envelope to be put in another big envelope addressed to Vice Principal , Asansol Girls' College and marked with the name of the Job, Name address and Phone No of the contractor and submitted in college office to drop in Tender box on or before **24.04.2023 upto 3 p.m.**

During Tender opening envelope mkd (1) is to be opened first and if everything is found o.k. and accepted by Tender committee envelope mkd(2) is to be opened . Offered price is to be noted in the chart. Successful Tender as decided by tender committee is to be marked (VIZ-L-1)and necessary work order (W.O) is to be issued in his favour. After acceptance of w.o. Notice is to be given to successful tenderer to submit security deposit (S.D) of Rs. 5000.00 in Bank draft and in favour of Vice Principal, Asansol Girls' College and advice him to start the job as per time schedule in W.O. After this all unsuccessful tenderers are to be informed to get refund of their E.M. E.M. of successful tenderers is to be kept along with S.D. This total S.D. money is to be refunded to the contractor after expiry of Defect liability period as mentioned in W.O. and necessary clearance of college Authority.

The contractor is advised to **fill up the format** in rate, Amount Column and total offered amount (Price Bid Amount) with his signature and stamp and submit the Tender in college office on or before **24.04.2023** within 3 p.m.


Signature of Vice Principal
Asansol Girls' College
Vice-Principal
Asansol Girls' College



Subject: Rebuild of Broken existing brick (C.B.W.) Boundary wall on east side (i.e. Rail line side) of college building with structural concrete (M20) frame work and cement brick work (1:6) with cement plaster (1:6) and cement wash.

FORMAT FOR PRICE BID

Sl. No	Description of Job	Quantity	Unit	Rate in Rs	Amount Rs.
1	Earth cutting, cleaning and transportation	5	Cu.M.		
2.	M-20 Concrete in r.c.c.	3	Cu.M.		
3.	F.B. Soling	3.2	Sq.M.		
4.	Reinforcement in r.c.c	240	Kg		
5.	Shuttering for r.c.c.	27.5	Sq.M.		
6.	125 C.B.W. with wire mesh in Every forth layer.	50	Sq.M.		
7.	Sand Cement plaster (6:1) 20M/M thick	96	Sq.M		
8.	2-coat cement wash	96	Sq.M		
Total Amount Rs.....					

Date:

Signature of contractor

Signature of Vice Principal
Asansol Girls' College

Vice-Principal
Asansol Girls' College

