

Asansol Girls' College

(NAAC Accredited with 'A' Grade)

(GOVT. SPONSORED)

Affiliated with The Kazi Nazrul University Dr. Anjali Roy Sarani, Asansol - 713304

Ph. 0341-2257107 (Day), 2254098 (Morn.), 2257600 (Principal), Fax: 0341-2257107

Website: www.agc.org.in • E-mail: mail@agc.org.in

Ref. No. 145/17

Date. 01.07.2017

Asansol Girls' College, Asansol-4

Subject: (1) One new septic tank for west side block of staff hostel.

(2) Dismantle and Rebuild of about 30' long surface drain with supply & construction of C.B.W. wall (one side) along north side college boundary wall behind new girls' hostel.

Total Estimate Cost for (1) & (2) = Rs. 62750.00

<u>Sealed quotation is invited from experienced parties for above two items detailed as follows and submitted within Ten days from the date of this letter in Tender box at Head Clerk Office.</u>

SI. No	Description of Job	Quoted Rate of Sl. No. 1 & 2	Name and Ph. No. Of the Party to offer quotation.
1.	Supply & construction of 1no 30 user septic tank with all necessary PVC pipe line connection with the existing system and disposing the clear effluent in surface drain. 3-nos chamber 1-2M SQ (I/S) x 1.6 M height up to U/S of Top cover. Necessary inlet chamber. All O/S wall to be 250 th C.B.W. (1:4 cement Mortar). I/S partition wall to be 125 th (1:3 Cement Mortar). R.C.C. (M20) bottom slab (1:10 Slope toward inlet in first two chamber) Over 75 th P.C.C.(1:3:6) over 75 th F.B. soling. 3nos 560 Dia C.I Manhole on 100 th R.C.C. top cover and one 50 Dia Ventilation pipe. 300 free board. A.S. Flooring & 1:4 cement plaster. All necessary details & I.S. specifications to be provided.		
2	Dismantling & Rebuild of boundary side wall of surface drain after clearing the roots & fell down of the tree. Damaged portion is about 30'lg. Alignment of the drain to be maintained true. Existing bricks to be reused after necessary dressing.		

Signature of Party.

Asansol Girls' College

Teacher-in-Charge Asansol Girls' College